



INDIANA DEPARTMENT OF TRANSPORTATION

COMMENT SHEET

Please provide your comments, concerns, and/or suggestions regarding the proposed US 27 Road and Bridge Maintenance project. Your comments are very important to us, and we sincerely appreciate your time and participation during the public involvement process. Please submit comments by Friday, May 15, 2020. Comments may be mailed or submitted via email to the contact below.

INDOT Greenfield Customer Care
 32 South Broadway
 Greenfield, IN 46140
 Phone: 1-855-463-6848
 Email: eastcentralin@indot.in.gov

Project: US 27 Road & Bridge Maintenance (Des. 1700811, 1702940 & 1800009)

Name: (please print) _____

Address: _____

Comments:

SIGNATURE: _____

US 27 Road & Bridge Maintenance Project Preliminary Project Information Sheet

- **Williamson Drive to SR 26 (Water Street) & From SR 67 (Votaw Street) to W CR 100N (Des. NO. 1700811)**
- Mill the existing pavement approximately 1.5 inches
- Partial & Full Depth Patching, as needed
- Replace Deficient Curb Ramps – Bring up to current
- Americans with Disabilities Act (ADA) Standards

- **SR 26 (Water Street) to SR 67 (Votaw Street) (Des. NO. 1800009)**
- Mill the existing pavement approximately 1.5 inches
- Partial & Full Depth Patching, as needed
- Replace Deficient Curb Ramps – bring up to current ADA standards
- 4-lane to 2-lane conversion, curb bump outs, parking
- Reduce US 27 from 2 through-lanes in each direction to 1 through-lane in each direction. Includes alternating left-turn lane at intersections.
- Add curb bump-outs to improve pedestrian safety
- Parallel parking on one side
- Back-in angled parking on the other side
- Remove traffic signals at Walnut Street & High Street

- **Bridge Maintenance – Meridian Street Bridge over Salamonie River (Des. NO. 1702940)**
- Patch the bridge deck, as necessary
- Replace the flexible bridge deck overlay

- Patch concrete columns, as necessary
- Paint the steel bridge railing, components, planters & light fixtures
- Clean concrete surfaces above the sidewalk or remove & replace masonry coating